

TABULATION OF BIDS

LETTING : 10070900 CALL : 191 COUNTIES : RENVILLE
 LETTING DATE : 07/09/10 9:30 A.M.
 JOB NO. : 100191 DISTRICT : 8
 STATE PROJECT : 6509-26 ROUTE : TH 71=4 LENGTH :
 CONTRACT NO. : 100191 START DATE: 08/02/10 COMPLETION DATE :
 NUMBER OF DAYS: 10 BRIDGE COUNT : 0

CONTRACT DESCRIPTION : CONCRETE REHAB (NEGOTIATED CONTRACT)
 CONTRACT LOCATION: LOCATED ON TH 71 FROM WEST JCT TH 212 TO 440 FT WEST OF
 TH 212

RECOMMENDATION: AWARD TO LOW BIDDER

I, THE UNDERSIGNED CERTIFY THAT THIS ABSTRACT IS A CORRECT TABULATION OF ALL BIDS RECEIVED ON THIS (THESE) PROJECT(S):
 THAT THE LEGAL REQUIREMENTS RELATING TO COMPETITIVE BIDDING ON PUBLIC PROJECTS HAVE BEEN COMPLIED WITH: THAT SAID BIDS
 WERE OPENED IN PUBLIC AND AWARD HAS BEEN MADE TO THE LOWEST RESPONSIBLE BIDDER.

APPROVED: _____ STATE AID OR CONSTRUCTION ENGR
 _____ ASST. DIV. DIRECTOR, OPERATIONS

RANK	VENDOR NO./NAME	TOTAL BID	% OVER LOW BID	% OVER EST
0	-EST- ENGINEER'S ESTIMATE	\$ 59,261.63	91.4574%	100.0000%
1	F250 FORBY CONTRACTING INC	\$ 64,797.00	100.0000%	109.3406%
2	W0056 WINDING ROAD CONSTRUCTION	\$ 88,639.50	136.7957%	149.5732%

LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
SECTION 0001 CONCRETE REHAB								
0010	2021501/00010 MOBILIZATION	LUMP	12000.00000	12000.00	7500.00000	7500.00	10000.00000	10000.00
0020	2301529/00011 REINFORCEMENT BARS (EPOXY COATED)	91.000 LB	2.65000	241.15	5.00000	455.00	10.00000	910.00
0030	2301538/00010 DOWEL BAR	109.000 EACH	10.50000	1144.50	15.00000	1635.00	20.00000	2180.00

T A B U L A T I O N O F B I D S

LETTING : 10070900

CALL : 191

COUNTIES : RENVILLE

LETTING DATE : 07/09/10 9:30 A.M.

JOB NO. : 100191

DISTRICT : 8

STATE PROJECT : 6509-26

ROUTE : TH 71=4

LENGTH :

CONTRACT NO. : 100191

START DATE: 08/02/10

COMPLETION DATE :

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(0) -EST- ENGINEER'S ESTIMATE		(1) F250 FORBY CONTRACTING INC		(2) W0056 WINDING ROAD CONSTRUCTION	
		UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
0040 2301602/00021 DRILL & GROUT REINFORCEMENT BAR (EPOXY COATED)	83.000 EACH	17.78000	1475.74	15.00000	1245.00	12.50000	1037.50
0050 2301603/00454 JOINT REPAIR (TYPE A-1H) 1/2"	1747.000 L F	1.00000	1747.00	2.00000	3494.00	3.00000	5241.00
0060 2301603/00674 LONGITUDINAL JOINT REPAIR (TYPE A-5H) 1/4"	528.000 L F	1.00000	528.00	2.00000	1056.00	2.50000	1320.00
0070 2301603/00676 LONGITUDINAL JOINT REPAIR (TYPE A-5H) 1/2"	1056.000 L F	1.50000	1584.00	2.00000	2112.00	3.50000	3696.00
0080 2301603/00745 CONTRACTION JOINT REPAIR (TYPE C-3D)	24.000 L F	93.75000	2250.00	95.00000	2280.00	150.00000	3600.00
0090 2301604/00080 CONCRETE GRINDING	1600.000 S Y	5.00000	8000.00	6.16000	9856.00	6.20000	9920.00
0100 2301604/00140 PAVEMENT REPLACEMENT SINGLE LANE (TYPE D-1)	166.000 S Y	100.00000	16600.00	150.00000	24900.00	200.00000	33200.00
0110 2301608/00104 SEAL CONCRETE PAVEMENT JOINTS (3725)	514.000 LB	4.26000	2189.64	6.00000	3084.00	7.50000	3855.00
0120 2301618/00221 SPOT SURFACE REPAIR (TYPE B-2A)	4.000 S F	53.40000	213.60	50.00000	200.00	200.00000	800.00
0130 2563601/00010 TRAFFIC CONTROL	LUMP	11000.00000	11000.00	6500.00000	6500.00	10000.00000	10000.00
0140 2580603/00010 INTERIM PAVEMENT MARKING	960.000 L F	0.30000	288.00	0.50000	480.00	3.00000	2880.00
SECTION TOTALS		\$	59,261.63	\$	64,797.00	\$	88,639.50
CONTRACT TOTALS		\$	59,261.63	\$	64,797.00	\$	88,639.50